

**EXHIBIT 3  
EXAMPLE OF ON-SITE NOTICE:**



## Radon Test in Progress

<b>REQUIRED CLOSED-BUILDING PROTOCOL</b>	
For tests lasting less than 4 days, initiate closed-building conditions 12 hours prior to the test. <b>MAINTAIN CLOSED-BUILDING CONDITIONS THROUGHOUT THE TEST PERIOD.</b>	
Required Closed-building Conditions	
<b>Windows</b>	<b>Keep closed</b> <i>(on all levels of the building including areas not being tested).</i>
<b>External doors</b> (except for momentary entry and exit)	
<b>Heating and Cooling Systems</b>	<b>Set to normal</b> <i>occupied operating condition with normal temperatures between about 65° to 80° F.</i>
<b>Whole House Fans</b>	<b>Do not operate.</b>
<b>Fireplaces</b> including those that burn solid, liquid, or gas fuels (unless they are the primary/normal sources of heat for the building)	
Any other system that may temporarily draw air into and out of the building	
Clothes dryers	<b>Avoid excessive operation.</b>
Range hoods	
Bathroom Fans	
<b>Do not disturb test devices.</b> The detectors cannot be moved, covered or have their performance altered during the test.	

Any test interference that is detected will be documented in the report, and may nullify the test results. We thank you for your cooperation in ensuring this test contributes to a safe and healthy home

Sincerely, \_\_\_\_\_ Phone (XXX) XXX-XXX